

Lifes Awesome

Ventures

C-One Industrial Park, Rodolfo Palaez Blvd., Kauswagan, Cagayan De Oro City
0939-9264230 / 09173082354 | james@brownjourney.com

COMMERCIAL AND TECHNICAL QUOTATION

Supply, Delivery, Installation, Testing and Commissioning of Electronic Low-Voltage Systems - MAB Building

Preliminary budgetary quotation based on the submitted MAB Electronic Plans

PREPARED FOR Mr. Dave V. Hembrador, Chairman & CEO Biztech IT Solutions Corporation 1387 Bontong, Camaman-an Cagayan de Oro City 9000, Philippines	QUOTE DETAILS Status: Preliminary Budgetary Draft Date: 25 August 2026 Validity: 45 calendar days Pricing: VAT Exclusive
PROJECT LOCATION MAB Building	ATTENTION Mr. Dave V. Hembrador, Chairman & CEO

Dear Mr. Hembrador,

Lifes Awesome Ventures Inc. is pleased to submit this preliminary quotation for the supply, delivery, installation, testing and commissioning of the electronic low-voltage systems indicated in the submitted MAB Electronic Plans.

SCOPE AND PRICING

A. Shared MDF, IDFs, Structured Cabling and Wireless Network System				
QTY	UNIT	DESCRIPTION / ACTIVITY	UNIT PRICE	AMOUNT
9	BOX	A1 - Pure-copper Hikvision CAT6 UTP cable, 305 meters per box	P 8,450.00	P 76,050.00
5	SET	A2 - 24-port CAT6 patch panel loaded with snap-in connectors	P 8,600.00	P 43,000.00
12	PC.	A3 - 24-slot 1U horizontal cable manager	P 3,500.00	P 42,000.00
10	ROLL	A4 - Five-meter Velcro cable tie	P 250.00	P 2,500.00
100	PC.	A5 - M6 cage nuts and rack screws	P 35.00	P 3,500.00
97	SET	A6 - D-Link CAT6 keystone jack with faceplate and outlet box	P 680.00	P 65,960.00
2	BOX	A7 - Passthrough CAT6 RJ45 connectors	P 1,550.00	P 3,100.00
1	LOT	A8 - CAT6 patch cords, equipment cords, labels and remaining rack accessories	P 43,640.00	P 43,640.00
8	UNIT	A9 - TP-Link AX3000 ceiling-mounted Wi-Fi 6 access point	P 12,000.00	P 96,000.00
1	UNIT	A10 - TP-Link centralized hardware network controller	P 10,800.00	P 10,800.00
4	UNIT	A11 - TP-Link 24-port managed PoE+ switch with SFP+ uplinks	P 38,000.00	P 152,000.00
1	UNIT	A12 - TP-Link 48-port managed PoE+ switch with 10G SFP+ uplinks	P 104,000.00	P 104,000.00
1	SET	A13 - Complete 42U floor-mounted shared MDF data cabinet with fan, PDU and rack accessories	P 68,500.00	P 68,500.00
4	SET	A14 - Complete 18U wall-mounted shared IDF data cabinet with fan, PDU and rack accessories	P 32,400.00	P 129,600.00
1	LOT	A15 - OM3 multimode fiber-optic backbone, transceivers, ODFs, pigtails, patch cords and splicing	P 142,000.00	P 142,000.00
4	UNIT	A16 - APC 1.5/1.6 kVA UPS for shared floor IDFs	P 20,500.00	P 82,000.00
1	UNIT	A17 - APC 3 kVA online rack-mounted UPS for shared MDF	P 112,000.00	P 112,000.00
1	LOT	A18 - Shared main ELV cable trays, riser pathways, supports, hangers and containment for all systems	P 397,000.00	P 397,000.00
1	LOT	A19 - Installation, cable pulling, termination, labeling, network configuration, certification, testing and documentation	P 571,350.00	P 571,350.00
SECTION A SUBTOTAL				P 2,145,000.00

B. IP CCTV Surveillance System				
QTY	UNIT	DESCRIPTION / ACTIVITY	UNIT PRICE	AMOUNT
13	UNIT	B1 - Hikvision 4MP PoE network dome camera	P 5,600.00	P 72,800.00
5	UNIT	B2 - Hikvision 4MP weather-resistant PoE network bullet camera	P 5,400.00	P 27,000.00
1	UNIT	B3 - Hikvision 32-channel network video recorder	P 32,000.00	P 32,000.00
4	UNIT	B4 - 4TB surveillance-grade hard disk drive	P 14,500.00	P 58,000.00
5	UNIT	B5 - 24-port managed PoE CCTV switch with fiber uplinks	P 32,500.00	P 162,500.00

B. IP CCTV Surveillance System				
QTY	UNIT	DESCRIPTION / ACTIVITY	UNIT PRICE	AMOUNT
1	LOT	B6 - CCTV rack-mounting, patching and power-connection accessories within the shared MDF and IDFs	P 25,000.00	P 25,000.00
1	UNIT	B7 - 40-inch CCTV monitoring display	P 38,000.00	P 38,000.00
1	LOT	B8 - Hikvision CAT6 UTP cabling, OM3 fiber backbone, transceivers, ODFs and fiber termination	P 182,000.00	P 182,000.00
1	LOT	B9 - Camera mounts, junction boxes, connectors, branch conduits and supports	P 187,000.00	P 187,000.00
1	LOT	B10 - Installation, configuration, camera aiming, recording setup, testing, training and documentation	P 463,900.00	P 463,900.00
SECTION B SUBTOTAL				P 1,248,200.00

C. Public Address and Background Music System				
QTY	UNIT	DESCRIPTION / ACTIVITY	UNIT PRICE	AMOUNT
113	UNIT	C1 - Auveo 6W ceiling-mounted public-address speaker	P 1,200.00	P 135,600.00
10	UNIT	C2 - Zone remote-control wall plate	P 6,800.00	P 68,000.00
2	UNIT	C3 - Remote zone-paging microphone	P 20,500.00	P 41,000.00
1	SET	C4 - Digital audio matrix and zone-paging controller	P 40,000.00	P 40,000.00
2	UNIT	C5 - 500W six-zone public-address power amplifier	P 28,000.00	P 56,000.00
1	UNIT	C6 - Digital music and program-source player	P 18,000.00	P 18,000.00
1	LOT	C7 - PA rack-mounting, power-connection and termination accessories within the shared MDF and IDFs	P 20,000.00	P 20,000.00
1	LOT	C8 - Fire-retardant two-core speaker cabling, including quantity allowance	P 142,000.00	P 142,000.00
1	LOT	C9 - Branch conduits, supports, boxes and PA pathway materials	P 137,000.00	P 137,000.00
1	LOT	C10 - Installation, termination, programming, zone balancing, testing, training and documentation	P 380,600.00	P 380,600.00
SECTION C SUBTOTAL				P 1,038,200.00

D. IP-Based Nurse Call System				
QTY	UNIT	DESCRIPTION / ACTIVITY	UNIT PRICE	AMOUNT
1	SET	D1 - Yarward intelligent management host, management server/workstation and software	P 180,000.00	P 180,000.00
2	UNIT	D2 - Yarward nurse-station medical-care host with interactive display	P 68,000.00	P 136,000.00
44	SET	D3 - Door-side terminal and corridor-light combination	P 6,800.00	P 299,200.00
13	SET	D4 - Yarward bedside call terminal with handset	P 8,500.00	P 110,500.00
7	UNIT	D5 - Yarward bathroom emergency pull-cord station	P 4,500.00	P 31,500.00
1	LOT	D6 - Gateways, power supplies, control interfaces, isolators and software licenses	P 108,000.00	P 108,000.00
1	LOT	D7 - Initial spare components, specialized connectors and testing accessories	P 58,000.00	P 58,000.00
1	LOT	D8 - International freight, insurance, importation, customs and brokerage allowance	P 227,000.00	P 227,000.00
1	LOT	D9 - Two-core communication and power bus, boxes, branch conduits and local rough-in materials	P 148,000.00	P 148,000.00
1	LOT	D10 - Installation, programming, device addressing, testing, commissioning, training, warranty support and documentation	P 395,800.00	P 395,800.00
SECTION D SUBTOTAL				P 1,694,000.00

E. Cable Television Distribution System				
QTY	UNIT	DESCRIPTION / ACTIVITY	UNIT PRICE	AMOUNT
18	POINT	E1 - Complete cable television outlet with faceplate, connector and outlet box	P 2,850.00	P 51,300.00
1	LOT	E2 - Passive distribution equipment, splitters, taps and enclosures mounted within the shared MDF and IDFs	P 68,000.00	P 68,000.00
1	LOT	E3 - RG6/RG11 coaxial backbone and horizontal cabling	P 68,000.00	P 68,000.00
1	LOT	E4 - Connectors, grounding, termination and distribution accessories	P 40,000.00	P 40,000.00
1	LOT	E5 - Branch conduits, boxes, supports and containment	P 62,700.00	P 62,700.00

E. Cable Television Distribution System				
QTY	UNIT	DESCRIPTION / ACTIVITY	UNIT PRICE	AMOUNT
1	LOT	E6 - Installation, termination, signal testing, labeling and as-built documentation	P 130,000.00	P 130,000.00
SECTION E SUBTOTAL				P 420,000.00

PROJECT COST SUMMARY

A. Shared MDF, IDFs, Structured Cabling and Wireless Network System	P 2,145,000.00
B. IP CCTV Surveillance System	P 1,248,200.00
C. Public Address and Background Music System	P 1,038,200.00
D. IP-Based Nurse Call System	P 1,694,000.00
E. Cable Television Distribution System	P 420,000.00
TOTAL QUOTATION, VAT EXCLUSIVE	P 6,545,400.00

Amount in Words: Six Million Five Hundred Forty-Five Thousand Four Hundred Pesos Only, VAT Exclusive.

ADDITIONAL NOTES

- Tax Treatment.** All quoted prices are VAT exclusive. Applicable VAT shall be added only when required under the final commercial agreement or billing arrangement.
- Scope Basis.** This preliminary quotation is based on the submitted 34-page MAB Electronic Plans. Final quantities remain subject to approved technical submittals, coordinated shop drawings and physical site validation.
- Cabling Standard.** The drawing's nonstandard "Cat6E" notation has been interpreted as standards-compliant pure-copper Hikvision CAT6 UTP cabling.
- Shared MDF and IDFs.** The electronic systems shall share one 42U MDF and four 18U floor IDFs. Separate CCTV, PA, nurse-call and CATV equipment cabinets and UPS units are not included or charged separately.
- Shared Infrastructure.** The shared MDF and IDFs include common rack power distribution, UPS protection, fiber termination and primary ELV cable pathways. Each system retains its required internal mounting, patching and termination accessories.
- Equipment Selection.** Equipment descriptions are performance-based. Exact equipment models shall be finalized during technical submittal and approval.
- Drawing Interpretation.** Third Floor Plan A and Third Floor Plan B have been treated as alternative layouts and counted only once.
- CCTV Storage.** The CCTV allowance includes a 32-channel recorder and 16TB raw storage. Actual retention shall depend on resolution, compression, frame rate, recording schedule and site activity.
- Nurse Call Architecture.** The nurse-call solution uses an IP-connected management host and nurse-station hosts, with wired two-core signaling and power to field devices.
- Implementation Period.** Estimated project duration is 90-120 calendar days after notice to proceed, initial payment, approved technical submittals and confirmation of site readiness.
- Payment Schedule.** 50% down payment; 40% progress billing upon equipment delivery and substantial installation; and 10% upon testing, commissioning and turnover.
- Validity.** Quotation validity is 45 calendar days.
- Warranty.** Equipment carries a one-year manufacturer's warranty. Installation workmanship carries a three-month warranty from project acceptance.
- Exclusions.** Internet service, cable television subscription, recurring service charges, electrical panelboards, dedicated electrical circuits, major civil works, ceiling replacement, painting, permits and government fees are excluded.
- Variations.** Work resulting from revised layouts, inaccessible pathways or routes beyond the approved drawings shall be treated as variation work.

Respectfully submitted,

PREPARED BY

JAMES BROWN B. BETE

General Manager
Lifes Awesome Ventures Inc.